

Appendix 8.4 Construction Traffic Flows

This page is intentionally blank.

Appendix 8.4 Construction Traffic Flows

Construction traffic data

Existing - November 2018 Daily Two Way 18 hour AADT:

Location	Cars & Lights	HGV	Total
A968 site access	355	106	461
A968 Ulsta	375	124	499

Future Baseline - 2022 Daily Two Way 18 hour AADT:

Location	Cars & Lights	HGV	Total
A968 site access	366	109	475
A968 Ulsta	386	128	514

Construction - Daily Two Way 18 hour AADT:

Location	Cars & Lights	HGV	Total
A968 site access	123	52	175
A968 Ulsta	123	39	162

Total - Daily Two Way 18 hour AADT:

Location	Cars & Lights	HGV	Total
A968 site access	489	161	650
A968 Ulsta	509	167	676

This page is intentionally blank.